



AIA® Document G701® – 2017

Change Order

PROJECT: *(Name and address)*
Springstead High School Drainage
Improvements & Turf Field
3300 Mariner Blvd
Spring Hill, FL 34609

CONTRACT INFORMATION:
Contract For: Construction Management
Services
Date: 03-24-2026

CHANGE ORDER INFORMATION:
Change Order Number: 001
Date: 05-29-2026

OWNER: *(Name and address)*
Hernando County School District

8016 Mobley Rd.
Brooksville, FL 34601

ARCHITECT: *(Name and address)*
Long & Associates Architects/Engineers,
Inc.
4525 S Manhattan Ave
Tampa, FL 33611

CONTRACTOR: *(Name and address)*
Walbridge

777 Woodward Ave. Suite 300
Detroit, MI 48226

THE CONTRACT IS CHANGED AS FOLLOWS:

(Insert a detailed description of the change and, if applicable, attach or reference specific exhibits. Also include agreed upon adjustments attributable to executed Construction Change Directives.)

Per District request, the following work was added to the original scope of work via Proposal Request #1: Demolition and replacement of existing asphalt track with a new asphalt and rubber surface track. This Change Order is based on a Not To Exceed price for the anticipated additional scope of work pending receipt of final sub-base test results.

The original Contract Sum was	\$ 3,308,637.00
The net change by previously authorized Change Orders	\$ 0.00
The Contract Sum prior to this Change Order was	\$ 3,308,637.00
The Contract Sum will be increased by this Change Order in the amount of	\$ 915,094.00
The new Contract Sum including this Change Order will be	\$ 4,223,731.00

The Contract Time will be increased by Sixty (60) days.
The new date of Substantial Completion will be 09-30-2026

NOTE: This Change Order does not include adjustments to the Contract Sum or Guaranteed Maximum Price, or the Contract Time, that have been authorized by Construction Change Directive until the cost and time have been agreed upon by both the Owner and Contractor, in which case a Change Order is executed to supersede the Construction Change Directive.

NOT VALID UNTIL SIGNED BY THE ARCHITECT, CONTRACTOR AND OWNER.




ARCHITECT *(Signature)*

BY: Travis G. Steed, Vice President of
Architecture

*(Printed name, title, and license
number if required)*

6-1-26

Date




CONTRACTOR *(Signature)*

BY: Craig Vincent, Vice President of
Operations

(Printed name and title)

6/1/2026

Date



OWNER *(Signature)*

Shannon Rodriguez, Vice
Chair
(Printed name and title)

6/9/26

Date

Springstead High School Track Resurfacing

Springstead High School

Spring Hill, FL

Estimate Type: Not to Exceed

Site Area: 100,000 SQFT

Estimate Date: 06/01/2026

Division	Description	Combined Division Totals	
		Total Cost per SQFT	Total Cost per Division
01	General Requirements	\$0.20	\$20,000
02	Existing Conditions	N/A	N/A
03	Concrete	\$0.73	\$72,820
04	Masonry	N/A	N/A
05	Metals	N/A	N/A
06	Wood, Plastics & Composites	N/A	N/A
07	Thermal & Moisture Protection	N/A	N/A
08	Openings	N/A	N/A
09	Finishes	N/A	N/A
10	Specialties	N/A	N/A
11	Equipment	N/A	N/A
12	Furnishings	N/A	N/A
13	Special Construction	N/A	N/A
14	Conveying Equipment	N/A	N/A
21	Fire Protection	N/A	N/A
22	Plumbing	N/A	N/A
23	HVAC	N/A	N/A
25	Integrated Automation	N/A	N/A
26	Electrical	N/A	N/A
27	Communications	N/A	N/A
28	Electronic Safety & Security	N/A	N/A
31	Earthwork	\$2.25	\$224,902
32	Exterior Improvements	\$4.09	\$409,299
33	Site & U.G. Utilities	N/A	N/A

Total Construction Costs - Direct **\$727,020**

Construction Costs - Indirect

Construction Contingency	5.00%	\$36,351
Owner's Contingency	5.00%	\$36,351
Market Escalation		Excluded
General Contractor Bond	1.00%	\$15,267
Construction Management GC's		\$6,126
Construction Management Personnel		\$45,961
Builders Risk Insurance	0.07%	\$1,140
GL Insurance	0.60%	\$9,571
CM Fee on Work	4.25%	\$37,306
Total Construction Costs - Indirect		\$188,074

Total Construction Cost - NTE **\$915,094**

Springstead High School Track Resurfacing

Springstead High School

Spring Hill, FL

ESTIMATE TYPE: Not To Exceed

Building Area: 100,000 SQFT

6/1/2026

Div. No.	Description	Quantity	Unit	Unit Cost	Total Cost	Div. Total	Cost per SQFT
1	General Requirements	Division Total Cost				\$20,000	\$0.20
	Trade General Conditions	Sub-Division Total Cost				\$20,000	\$0.20
	Materials Testing	1	Allow	\$20,000.00	\$20,000		
		1	Allow				
	Temp Fencing	Sub-Division Total Cost				N/A	N/A
2	Existing Conditions	Division Total Cost				N/A	N/A
3	Concrete	Division Total Cost				\$72,820	\$0.73
	Foundations	Sub-Division Total Cost				N/A	N/A
	Concrete Accessories						
	Concrete Reinforcement						
	Foundation Wall Footings						
	Retaining Wall Footings						
	Basement Wall Footings						
	Column Spread Footings						
	Foundation Walls						
	Retaining Walls						
	Basement Walls						
	Concrete Columns						
	Concrete Pan Joist Floor Frame						
	Concrete Elevator Pits						
	Concrete - Other & Misc.						
	Concrete in Stair Pans & Landings						
	Slab on Grade	Sub-Division Total Cost				N/A	N/A
	Standard Slab on Grade						
	Structural Slab on Grade						
	Precast & Tilt-Up Concrete Systems	Sub-Division Total Cost				\$72,820.00	\$0.73
	Precast Structural Concrete						
	3203 - Concrete Curb Work	1	LS	\$72,820.00	\$72,820		
	Demo & dispose of existing concrete curb along inner track perimeter					In Above	
	Demo & dispose of existing concrete curb along outer track perimeter					In Above	
	Provide 6" x 12" concrete curb in place					In Above	
	Architectural Precast						
	Concrete on Metal Deck	Sub-Division Total Cost				N/A	N/A
4	Masonry & Stone	Division Total Cost				N/A	N/A
5	Metals	Division Total Cost				N/A	N/A
6	Wood, Plastics & Composites	Division Total Cost				N/A	N/A
7	Thermal & Moisture Protection	Division Total Cost				N/A	N/A
8	Openings	Division Total Cost				N/A	N/A
9	Finishes	Division Total Cost				N/A	N/A
10	Specialties	Division Total Cost				N/A	N/A
11	Equipment	Division Total Cost				N/A	N/A
12	Furnishings	Division Total Cost				N/A	N/A
13	Special Construction	Division Total Cost				N/A	N/A
14	Conveying Systems	Division Total Cost				N/A	N/A
21	Fire Suppression	Division Total Cost				N/A	N/A
22	Plumbing	Division Total Cost				N/A	N/A
23	HVAC	Division Total Cost				N/A	N/A
25	Integrated Automation	Division Total Cost				N/A	N/A
26	Electrical	Division Total Cost				N/A	N/A
27	Communications	Division Total Cost				N/A	N/A
28	Electronic Safety & Security	Division Total Cost				N/A	N/A
31	Earth Work	Division Total Cost				\$224,902	\$2.25
	Site Clearing	Sub-Division Total Cost				N/A	N/A
	Grading	Sub-Division Total Cost				N/A	N/A
	Excavation & Fill	Sub-Division Total Cost				\$224,901.67	\$2.25
	Excavation						
	3203 - Sub-Base Replacement	1	LS	\$221,578.00	\$221,578		
	Cut sub-base to finish grade, remove and dispose of offsite					In Above	

Springstead High School Track Resurfacing

Springstead High School

Spring Hill, FL

ESTIMATE TYPE: Not To Exceed

Building Area: 100,000 SQFT

6/1/2026

Div. No.	Description	Quantity	Unit	Unit Cost	Total Cost	Div. Total	Cost per SQFT
	Locate and provide stake out based on engineer points, laser grade to 1% and 0 planarity, compact to 95%				In Above		
	Laser grade high jump area of 556 SY				In Above		
	Pave track and high jump in D-zone area 1 with 1.5" of 1/2" binder HMA				In Above		
	Pave track and high jump in D-zone area 1 with 1.5" of 3/8" no rap custom design surface mix				In Above		
	Dig out and dispose spoils				In Above		
	Construct pole vault area 73SY				In Above		
	Install pole vault box				In Above		
	Pour concrete runway with 400PSI mix				In Above		
	Dig out and dispose spoils				In Above		
	Construct long jump runway, landing box with concrete curb & drainage				In Above		
	Construct triple jump and box with concrete curb & drainage				In Above		
	Subcontractor Bond	1	LS	\$3,323.67	\$3,323.67		
32	Exterior Improvements	Division Total Cost				\$409,299	\$4.09
	Site Concrete & Concrete Paving	Sub-Division Total Cost				N/A	N/A
	Site Asphalt Paving	Sub-Division Total Cost				N/A	N/A
	Site Improvements	Sub-Division Total Cost				\$409,298.75	\$4.09
	Chain Link Fencing						
	Track resurfacing						
	3203 - Track Resurfacing	1	LS	\$403,250.00	\$403,250		
	Installation fo approximately 5745 SY of Rekortan BSS Black		LS		In Above		
	5 year APT warranty		LS		In Above		
	Track striping per NFHS standards		LS		In Above		
	Subcontractor Bond	1	LS	\$6,048.75	\$6,048.75		
	Landscaping & Plantings	Sub-Division Total Cost				N/A	N/A
33	Utilities	Division Total Cost				N/A	N/A
	Underground & Site Utilities	Sub-Division Total Cost				N/A	N/A
Springstead High School			Total Construction Cost - Direct			\$727,000	\$7.27

STAFF POSITION		QUANTITY		1		2		3		4		5		6		7		8		9		10		11		12		13		14		15		16		17		18		19		20		21		22		23		24	
		Origin	Chk	Total Mo.	Jun 26	Jul 26	Aug 26	Sep 26	Oct 26	Nov 26	Dec 26	Jan 27	Feb 27	Mar 27	Apr 27	May 27	Jun 27	Jul 27	Aug 27	Sep 27	Oct 27	Nov 27	Dec 27	Jan 28	Feb 28	Mar 28	Apr 28	May 28																							

STAFF POSITION		QUANTITY																													
		Origin	Chk Total Mo.	Jun 26	Jul 26	Aug 26	Sep 26	Oct 26	Nov 26	Dec 26	Jan 27	Feb 27	Mar 27	Apr 27	May 27	Jun 27	Jul 27	Aug 27	Sep 27	Oct 27	Nov 27	Dec 27	Jan 28	Feb 28	Mar 28	Apr 28	May 28				
Project Staff																															
1	Project Director	Det	OK	-	0.50	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
2	Project Manager - Al Price	Det	ERR	1.0 mo	0.50	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
3	Assistant Project Manager	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
4	Superintendent - Pedro Toribio	Det	OK	2.0 mo	1.00	1.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
5	Assistant Superintendent	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
6	Safety Engineer	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
7	Project Engineer	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
8	Mechanical/Electrical Engineer	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
9	Project Coordinator	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
10	Engineering Manager	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
11	Cost Analyst - Courtney Meeks	Det	OK	0.2 mo	0.10	0.10	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
12	Project Coordinator - Freedom Allen	Det	OK	0.5 mo	0.50	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
13	Scheduler/Planner - Prakash Subet	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
14	Layout Engineer Crew(s) - 2 men	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
15	Precon	Det	OK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-			
TOTAL STAFF			OK	3.7 mo	2	2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			

**DO NOT OVERLAP THE PROJECT DURATIONS BELOW
THIS CHART IS USED TO CALCULATED DUMPSTERS AND UNIDENTIFIABLE CLEANUP AT THE BOTTOM OF THE GC WORKBOOK